



EXHIBIT B

General Information

Proposal Submitted To

Contact Name Michael Elkins
Account Name City of Green
Bill To 1755 Town Park Blvd P O Box 278 Green, OH 44232
Email melkins@cityofgreen.com

Location

Ship To Name Boettler Park
Ship To 5300 Massillon Rd North Canton, OH 44720
Is job located within the city limits?
Created Date 12/9/2024

Payment Terms

Net upon completion - 1 1/2% per month (18% APR) finance charge on all balances over 30 days. We propose to furnish material and labor according to the specifications below, for the sum of:

Table with 4 columns: Product, Sales Price, Quantity, Total Price. Rows include Court Rebuild, Walking Path, and a Total Price row.

Site Terms

Material is guaranteed to be as specified and work will be according to standard practices. Changes from specifications involving additional costs will only be done upon a written order and will become an extra above the estimate. All agreements contingent upon strikes, accidents, or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Worker's Compensation Insurance. This proposal may be withdrawn if not accepted within 30 days.

Created By Brady Yoder

Scope

- 1. Pull back fence around court to gain access to site. Existing fencing and basketball hoops to remain.
2. Mill out all asphalt inside of fence line down to stone base (assume 4-6" of asphalt to be milled)
3. Excavate ground 10" along outside of court to connect parking lot walking path, basketball court, and main road entrance (see attached drawing. 275'x8')
4. Rough grade excavated area and prep for stone. Install drain line under path to allow water to pass under walking path and continue underneath road as currently intended
5. Install 6" limestone base for walking path and fine grade
6. Fine grade existing stone base under basketball court and add new limestone as needed to achieve desired slope. Assume adding 1" of new limestone.
7. Pave 2.5" of binder asphalt over basketball court and walking path. (Roughly 926SY total)
8. Pave 1.5" of virgin mix wearing asphalt over basketball court and walking path.
9. Once asphalt has cured (28 days), make any minor patches as necessary to prep for acrylic coating
10. Install 2 coats of acrylic resurfacer to basketball court (Roughly 620SY)
11. Install 2 coats of acrylic color coating system to basketball court (colors to be determined by owner)
12. Stripe 1 regulation basketball court with white textured line paint
13. Replace removed portion of fencing
14. Fine grade, seed and straw distressed areas around court and walking path.

*Vasco not responsible for growth of new grass following seed and straw. Project is priced as tax exempt, non-prevailing wages, and through NCPA contract. We are assuming existing stone base is adequate. If existing base under court is not adequate, it may need to be addressed via CO. Vasco NCPA/Omnia Contract info: Region 14 ESC - TX
Contract Number: 08-43*



Acceptance

Work performed in addition to the specifications listed above require additional charges. Upon acceptance, please sign and return one copy.

ACCEPTANCE: The above specifications, conditions, and price(s) are acceptable. I authorize Vasco to do the work as specified.

Date Of Acceptance: _____

Acceptance Signature: _____